CALIFORNIA DEPARTMENT OF FORESTRY & FIRE PROTECTION
OFFICE OF THE STATE FIRE MARSHAL
FIRE ENGINEERING - BUILDING MATERIALS LISTING PROGRAM

LISTING SERVICE

LISTING No.   7165-1130:256

CATEGORY: Control Unit (Non High-Rise)

LISTEE: Honeywell International, Inc., 1500 W. Dundee Rd., Arlington Heights, IL 60004
Contact: Bob Hodgson (847) 797-4403 FAX (847) 797-3664

DESIGN: Model XLS3000 fire alarm control units. Local, auxiliary, remote station (PPU), proprietary (PPU), central station (PPU), automatic, manual, waterflow and sprinkler supervisory services. Refer to listee's data sheet for detailed product description and operational considerations. System components:

ACM-8R/-16AT/-24AT/-32A/-48A	Annunciator Control Modules
ACPS-2406	Addressable/Charger Power Supply
AEM-16AT/-24AT/-32A/-48A	Annunciator Expander Modules
AFM-16A/-16AT/-32A	Annunciator Fixed Modules
XLS-AKS-1B	Annunciator Key Switch
AMPS-24	Addressable Main Power Supply
APS-6R	Auxiliary Power Supply
ARM-4	Auxiliary Relay Module
BB-100/-200	Battery Box
BMP-1	Blank Module
BGRA-SCS, BGRB-SCS,	Smoke Control Enclosures for SCS Modules
CEF-SCS, RSA-SCS, RSB-SCS,	Smoke Control Enclosures for SCS Modules
RSC-SCS, RSD-SCS, RSE-SCS	Smoke Control Enclosures for SCS Modules
BP-4	Battery Panel
XLS-BP2-4	Dress Panel
BX-501	Intelligent Detector/Sensor Base
B-501	Intelligent Base
B-710LP	Intelligent Detector Base
CAB-4 Series	Enclosure
CHG-120	Battery Charger
CHS-4L/-4MB/-4N/-6/-M3/-PS/*-BH1	Chassis
XLS3000-CPUND/-CPUD	CPU Board
CRE-4	Control Relay Expander
CRM-4RK	Control Relay Module
CRT-2	Display Terminal
DCM-4RK	Dual Channel Module
DP-1B	Blank Panel
DP-DISP	Display Dress Panel
DPDW-1B, DPSW-1B, XPDP	Dress Panels
VP-2B	Dress Panel
DPI-232	Direct Panel Interface
FCPS-24	Field Charger/Power Supply
ICE-4	Indicating Control Expander
ICM-4RK	Indicating Circuit Module
IZE-A	Initiating Zone Expander
IZM-8RK	Initiating Zone Module
ISO-X	Isolator Module
LCD-80/-160	Liquid Crystal Display Module
LCM-320/LEM-320	Loop Expander Module
LDM-32/-E32/-R32	Lamp Driver Modules

MP-1B	Blank Panel
MPS-24B	Power Supply Module
XLS-MPS	Addressable Manual Pull Station
XLS-NCA-2	Network Control Annunciator
NCM-W/-F	Network Control Module
N-ELR	End of Line Resistors
NFS-LBB/-LBBR/-BB-25/-BB-17	Battery Box
XLS-PRN-6	Printer
R-120/-2.2K/-27K/-470/-47K	End of Line Resistors
RA-400/-400Z	Remote Annunciators
RKS-S	Remote Security Keyswitch
RPJ-1	Remote Paging Jack
RPT-W/-F/-485W/-485WF	Repeater
RM-1/-1SA	Remote Microphone
SCS-8	Smoke Control Station
SCE-8	Smoke Control Expander
STS-1	Security Tamper Switch
TM-4	Transmitter Module
TR-A4/-B4/-C4/-D4	Trim Ring
UDACT	Universal DACT
UZC-256	Universal Zone Coder
VCE-4	Voice Control Expander
VCM-4RK	Voice Control Module
VS4095	Keltron Remote Printer
XP5-C/-M	Transponder
XPC-8	Transponder Control Module
XPIQ	Transponder Quad Intelligent Audio Module
XPM-8/-8L	Transponder Monitor Modules
XPP-1	Transponder Processor
XPR-8	Transponder Relay Module

INSTALLATION: In accordance with listee's printed installation instructions, applicable codes and ordinances and in a manner acceptable to the authority having jurisdiction.

MARKING: Listee's name, model number, electrical rating and UL label.

APPROVAL: Listed as fire alarm control units for use with separately listed compatible initiating and indicating devices. This control unit can generate the temporal code pattern fire alarm signal as required per NFPA 72, 2002 Edition. Refer to listee's Installation Instructions Manual for details.

This control unit meets the requirements of UL-864, 8th Edition Standard.

NOTE: For *Fire Alarm Verification* feature (delay of fire alarm signal), the maximum Retard/Reset/Restart period shall not exceed 30 seconds.

XLF: 7165-0028:224

06-29-2006 jew

Date Issued: **JUNE 6, 2007**   *Listing Expires June 30, 2008*

A*uthorized By:* **MIKE TANAKA**, *Senior Deputy State Fire Marshal*
Program Manager