

CALIFORNIA DEPARTMENT OF FORESTRY & FIRE PROTECTION
OFFICE OF THE STATE FIRE MARSHAL
FIRE ENGINEERING - BUILDING MATERIALS LISTING PROGRAM

LISTING SERVICE

LISTING No. 7770-0675:105 Page 1 of 1

CATEGORY: Valves/Switches

LISTEE: Central Sprinkler Company, 451 N. Cannon Avenue, Landsdale, PA 19446
Contact: Gwendolyn A. DiChiaro (401) 781-8220 ext. 408 Fax (401) 781-7317

DESIGN: Model 513 D/R Residential Floor Control Valve and Test Assembly. Unit is an integrated assembly for in-line installation within 1, 1 ½ and 2 inch fire protection systems that provides flow detection switches, pressure gauges and full flow test connection outlet for flow testing. Refer to listee's data sheet for additional detailed product description and operational considerations.

RATING: Working pressure: 175 psi

INSTALLATION: In accordance with listee's printed installation instructions, NFPA 72 and applicable codes and ordinances. These devices are intended to be installed between riser or supply main and the sprinkler system for the purpose of testing water flow indicators and providing system drainage.

MARKING: Listee's name, model number, rating, and UL label.

APPROVAL: Listed as floor control valve and test assembly for fire protection systems. Suitable for above ground and indoor installation.

11-14-2002 JEW



This listing is based upon technical data submitted by the applicant. CSFM Fire Engineering staff has reviewed the test results and/or other data but does not make an independent verification of any claims. This listing is not an endorsement or recommendation of the item listed. This listing should not be used to verify correct operational requirements or installation criteria. Refer to listee's data sheet, installation instructions and/or other suitable information sources.

Date Issued: **JUNE 11, 2003**

*Listing Expires **June 30, 2004***

Authorized By: **DIANE K. AREND, Senior Deputy
Program Manager**