CALIFORNIA DEPARTMENT OF FORESTRY & FIRE PROTECTION OFFICE OF THE STATE FIRE MARSHAL

FIRE ENGINEERING - BUILDING MATERIALS LISTING PROGRAM

LISTING SERVICE

LISTING No. 7165-1062:113 Page 1 of 1

CATEGORY: Control Unit/Non High-Rise

LISTEE: Detection Systems, Inc., 130 Perinton Parkway, Fairport, NY 14450

Contact: Frank Mioduszewski (585) 223-4060 FAX (585) 421-4263

DESIGN: Model *DS7400Xi 3+ and *DS7400Xi 4+ fire alarm control units. Coded or noncoded,

automatic, manual, local, central station, remote station, waterflow, and sprinkler supervisory service. Refer to listee's printed data sheet for additional detailed product

description and operational considerations. *System components:

*DS7400Xi 3+, *DS7400Xi 4+ Control Panel

DS7433 8-Zone Expansion Module DS7416i, DS7416iF Communication Module

DS7445, DS7447, DS7448 Keypads *DS7445i, *DS7447i, *DS7447E Keypads DS7420i Fire Module

DS7430, DS7432 Multiplex Expander Module

DS7460, *DS7460i 2-Zone Expander

DS7481 Single Phone Line Monitor

DS7488 Relay Board

3100-0200 AAGARD Radio Interface Module

AE-TR-16 Transformer

DS9484 Remote NAC Expander
DS7430, DS7436 Multiplex Expander Module
DS7480 Bell Supervisory Board
DS7465 *DS7465i Input/Output Multiplex Module

DS7465, *DS7465i Input/Output Multiplex Module
DS7457, *DS7457iF Single Zone Multiplex Input Module
*DS7461i Single Zone Multiplex Input Module

INSTALLATION: In accordance with listee's printed installation instructions, applicable codes & ordinances

and in a manner acceptable to the authority having jurisdiction.

MARKING: Listee's name, model number, electrical rating, and UL label.

APPROVAL: Listed as fire alarm control units for use with separately listed compatible initiating and

indicating devices. Refer to listee's Installation Instruction Manual for details.

These control units can generate a distinctive three-pulse Temporal Pattern Fire Alarm

Evacuation Signal (for total evacuation) in accordance with NFPA 72, 1999 Edition.

NOTE: 1. Burglary and other non-fire functions were not examined.

2. For Fire Alarm Verification Feature (delay of fire alarm signal), the maximum

Retard/Reset/Restart period shall not exceed 30 seconds.

*Rev. 02-04-04



This listing is based upon technical data submitted by the applicant. CSFM Fire Engineering staff has reviewed the test results and/or other data but does not make an independent verification of any claims. This listing is not an endorsement or recommendation of the item listed. This listing should not be used to verify correct operational requirements or installation criteria. Refer to listee's data sheet, installation instructions and/or other suitable information sources.

Date Issued: FEBRUARY 4, 2004 Listing Expires June 30, 2004

Authorized By: **DIANE K. AREND**, Senior Deputy

Program Manager